

Last Date for submission of quotations: 20th January 2017 up to 12.00 pm

Sealed quotations are invited for supply, erection & commissioning of Main Distribution Panel and Internal Electrical Work for Focus Incubation Centre, NITRA, Ghaziabad

The following work related to supply, erection & commissioning of main distribution panel and internal electrical work for Focus Incubation Centre, NITRA is to be carried out:

(I) MAIN DISTRIBUTION PANEL				
Design, manufacture, supply, installation testing and commissioning of 2 mm thick MS sheet steel fabricated cubicle type sub-distribution board, dust and vermin proof, complete with hinged detachable and lockable doors. Main distribution board shall be INDOOR type floor mounting and of dead front construction, complete with interconnections by copper tapes/wires and painting. Cable entry from top/bottom shall be provided in all the panels.				
(A) INCOMER				
BOQ DESCRIPTION	MAKE	Qty	Unit Price (Rs.)	Total Cost (Rs.)
320A 4P 36kA MCCB TM Release, Type: DN3B-400D, 415V AC, 50Hz	L&T	1 No.		
Extended Rotary Handle for DN3B, DN3 MCCB	L&T	1 No.		
DN3-400 Spreader Terminals - 4 Pole (Set of 8)	L&T	1 No.		
Red Gen Next LED Indicator 22.5 mm, Voltage: 240V AC	ESBEE	1 No.		
Yellow Gen Next LED Indicator 22.5 mm, Voltage: 240V AC	ESBEE	1 No.		
Blue Gen Next LED Indicator 22.5 mm, Voltage: 240V AC	ESBEE	1 No.		
Energy Meter & VAF+PF Meter EM1200, Accuracy: Cl0.5, With RS485 port	CONZERV	1 No.		
300/5A Acc. Class: 1,10VA, Resin Cast Ring type Current Transformer	TRINITY	1 No.		
6A 1P 10kA, B-Curve MCB	L&T	3 No.		
32A Isolating link	SIEMENS	1 No.		
(B) OUTGOING FEEDER				
BOQ DESCRIPTION	MAKE			
6A 2P 10kA C-Curve MCB, Type: xC60	SCHNEIDER	40 No.		
16A 50kA MPCB, TM Release (Short Circuit & Overload Protection), Range: 11.00-16.00, Type: MOG-H1 (Rotary Type)	L&T	10 No.		
16A 2P 10kA C-Curve MCB, Type: xC60	SCHNEIDER	4 No.		
32A 4P 10kA C-Curve MCB, Type: xC60	SCHNEIDER	3 No.		

(II) INTERNAL ELECTRICAL WORKS				
DESCRIPTION	Make	Qty	Unit Price (Rs.)	Total Cost (Rs.)
Wiring for light point, fan point, exhaust fan point, call bell point with 1.5 sqmm. PVC insulated copper conductor single core cable in surface/recessed medium class PVC conduit with 6 Amp. modular switch, modular plate, suitable GI box and earthing the point with 1.5 sqmm FRLS PVC insulated copper conductor single core cable etc as required.		20 Nos.		
2X1.5 sq mm	Plaza/Havels	500 Mtrs		
4X1.5 sq mm	Plaza/Havels	300 Mtrs.		
4X4 sqmm	Plaza/Havels	250 Mtrs.		
2X1.5 sq mm + 1X1.5 sq mm	Plaza/Havels	600 Mtrs.		
3.5 CORE 240 Sqmm Alu Arm	Plaza/Havels	70 Mtrs.		

Sealed quotations are invited from reputed manufacturers/ Suppliers for above requirement. For any query, please contact our office at Sector-23, Raj Nagar, Ghaziabad- 201002. Phone No. 0120-2786434/451, email: mail@nitratextile.org. Last date for submission of quotations is 20-01-2017 up to 12.00 p.m. Quotations will be opened on 20-01-2017 at 03.00 pm.

Terms & Conditions:

1. No Quotations shall be entertained, if sent through e-mail, fax, telex or telegraphic mode.
2. Quotations should be inclusive of all taxes (without any concessional form), duties, packing-forwarding, erection charges, loading- unloading, insurance and any other incidental charges.
3. The quoted price should be written both in words and in figures. The quotation shall also show the amount for each item, the total of each section and the grand total of the whole quotation.
4. In case of conflict between the figures and words in the rates, the latter shall prevail.
5. Rates quoted should be valid for a period of 90 days.
6. Warranty should be of at least one year.
7. Organization profile needs to be submitted along with the quotation, which should include profile of the organization, copy of VAT registration, PAN, Service Tax etc., and list of clients along with address and telephone no., to which similar nature of services has been rendered by the organization.

Terms of Payment:

1. 20% advance will be paid against confirmation/acceptance of orders.
2. 40% payment will be made on supply of Items in all respect.
3. 30% payment will be made on completion of work in all respect.
4. Balance 10% payment will be made after 1 year from the date of completion of work in all respect.